

PRODUCT FEATURES

MINIMAL RECESSED HEIGHT

Width: 3.0" Height: 3.5"

ONE-PIECE EXTRUDED ALUMINUM HOUSING

Housing ensures straighter rows and consistent lens retention


MULTIPLE CEILING SYSTEMS

Engineered to be installed in multiple grid systems or hard ceiling applications

120/277VAC 0-10 VOLT DIMMING TO 1% STANDARD

UP TO 127.2 LUMENS PER WATT

ORDERING GUIDE EX: 3R - 20 - HD - 30 - UNV - T1 - WH - EM



SERIES	LENGTH	OUTPUT		CCT	VOLTAGE	MOUNTING		FINISH
3R								
	XX FT	VHD 1250 LM/FT	LD 500 LM/FT	30 3000K	UNV 120-277V	T1 1" T-Grid	SC Screw Slot Grid	WH White
	2' Increments EX: 20' = 20	HD 1000 LM/FT	VLD 250 LM/FT	35 3500K	347 ¹ 347V	T9 9/16" T-Grid	OF Overlapping Flange	BLK Black
		MD 750 LM/FT	CD Custom	40 4000K		TG 1" T-Teg Grid	SF Spackle Flange	
						TG9 9/16" T-Teg Grid		

OPTIONS

CRI	INTEGRATED CONTROLS ³		RATING	OPTICAL
BLANK = 80 CRI	OS Occupancy Sensor	CP Chicago Plenum	BLANK = LAMBERTIAN	
C90 90 CRI	DOS Daylight Occupancy Sensor	WW ⁴ Wall Wash, Direct		

FOR INDIVIDUALS		FOR LINEAR RUNS ^{5,6}					
		EM			EC		
		EMERGENCY BATTERY PACK	QUANTITY PER RUN ⁶	POSITION IN RUN ⁶	EMERGENCY CIRCUIT	QUANTITY PER RUN ⁶	POSITION IN RUN ⁶
EM ² Emergency Battery							
EC Emergency Circuit							

ORDERING NOTES

- EM NOT AVAILABLE WITH 347V.
- EM NOT AVAILABLE WITH 2' FIXTURES.
- FOR INDIVIDUAL FIXTURES, SENSOR LOCATED AT POWER FEED END. FOR RUNS, A SENSOR IS INSTALLED INTO EACH FIXTURE IN RUN, EX. 2 SENSORS ARE INSTALLED IN A 16 FT RUN (1 SENSOR IN EACH 8 FT FIXTURE)

EMERGENCY OPTION NOTES

- INTEGRATED CONTROLS NOT AVAILABLE WITH WALL WASH.
- EM AND EC QUANTITY IS NOT TO EXCEED NUMBER OF DISCRETE FIXTURE SECTIONS IN A ROW.
- EM AND EC POSITION REFERS TO WHICH FIXTURE IN THE RUN THAT WILL BE POWERED BY THE EM/EC CIRCUIT. POSITION OPTIONS: S=STARTER, J=JOINER, E=ENDER EX: 3R-20-HD-35-UNV-T1-WH-EM2SJ

ooo STARTER ooo JOINER ooo ENDER ooo


PHOTOMETRICS

3R-04-HD-35-UNV-XX-X

Total Lumens: 4,130
Ratio: 0% Up & 100% Down
Wattage: 32.9
Efficacy: 125.3 LM/W
Fixture Length: Four Feet

ZONAL LUMEN SUMMARY

Zone	Lumens	% Fixt
0 - 30	1192.7	28.9
0 - 40	1913.9	46.3
0 - 60	3270.4	79.2
0 - 90	4128.8	100.0
90 - 180	1.13	0.0
0 - 180	4129.9	100.0




3R-04-HD-35-UNV-XX-X-WW

Total Lumens: 4,056
Ratio: 0% Up & 100% Down
Wattage: 32.9
Efficacy: 123.1 LM/W
Fixture Length: Four Feet

ZONAL LUMEN SUMMARY

Zone	Lumens	% Fixt
0 - 30	1302.5	32.1
0 - 40	2069.1	51.0
0 - 60	3395.8	83.7
0 - 90	4055.8	100.0
90 - 180	0.23	0.0
0 - 180	4056.0	100.0



ENERGY CONSUMPTION

WATTS PER LINEAR FOOT

DIRECT (LAMBERTIAN) LIGHT

	VHD	HD	MD	LD	VLD
W/FT	10.0	8.2	6.5	4.0	2.1
LM/FT	1210	1014	761	509	246
LM/W	120.9	123.1	117.4	127.2	119.3

DIRECT (WALL WASH) LIGHT

	VHD	HD	MD	LD	VLD
W/FT	10.0	8.2	6.5	4.0	2.1
LM/FT	1210	1014	761	509	246
LM/W	120.9	123.1	117.4	127.2	119.3

OPERATION

Light Engine:

The 3R is available in 3000K, 3500K and 4000K CCT all within a 3-Step MacAdam Ellipse and has a standard CRI of 80+. Optional 90+ CRI available.

Optics:

The back-lit extruded acrylic lens ensures high efficiency light output, in a minimal form factor for a clean, evenly illuminated surface with minimal glare.

Optional Wall Wash:

Asymmetric extruded aluminum reflector with recessed extruded acrylic lens to achieve a superior wall uniformity while minimizing glare.

Electrical:

Class 2 programmable (factory pre-set) premium power supply, 120-277VAC input. Power factor >0.9. THD <15%. Integral Surge Protection to 2KV.

Dimming:

The 3R comes standard with 0-10V dimming down to 1%.

Emergency Battery Pack:

Emergency Battery Pack has been engineered to exceed UL minimum safety standards. For most fixtures, the entire direct portion of the fixture will be illuminated by the EM Battery Pack. For 8' VHD, 10' HD and VHD, and 12' MD, HD, and VHD, only the first portion of the fixture will be illuminated by the EM battery pack. "Quantity per Run" refers to the number of fixtures in the run that will be supplied with an emergency battery pack. "Position in Run" refers to which fixture in the run that will contain the battery. Position options are Starter (S), Joiner (J), or Ender (E). For example, a 24' run needing two emergency battery packs, one in the starter and one in the joiner, would be ordered as EM2SJ. When a joiner is selected, battery packs are always supplied in 8' fixtures before 6' fixtures in that run.

Emergency Circuit:

Emergency Circuit fixtures are engineered so that the entire fixture is wired to the emergency circuit. "Quantity per Run" refers to the number of fixtures in the run that are wired to the emergency circuit. "Position in Run" refers to which fixture in the run that will be powered by the Emergency Circuit. Position options are Starter (S), Joiner (J), or Ender (E). For example, a 24' run with needing two emergency sections, one in the starter and one in the joiner, would be ordered as EC2SJ. When a joiner is selected, Emergency Circuits are always supplied in 8' fixtures before 6' fixtures in that run.

GENERAL

Warranty:

Ten (10) Year limited warranty from date of shipment.

Lumen Maintenance:

Rated for 85% initial lumen output at 85,000 Hours of operation, operated at 25°C ambient temperature; per TM-21 Guidelines published by the Illuminating Engineering Society (IES).

Certifications:

All Luminaires are UL/cUL Listed to UL 1598 Standards and approved for Indoor use in Dry/Damp Locations. Luminaires are IC rated.

MECHANICAL

Housing Construction:

Extruded Aluminum 6063-T5 alloy outer housing and LED tray with die-formed steel internal components for strength, alignment and mounting attachment. Our high-quality die-cast end caps are engineered to conceal all fasteners and to retain the sealing gaskets on the inside of the fixture while completing the clean and minimalistic look of this luminaire.

Alignment/Assembly:

The alignment system employs a four-point alignment and attachment method, designed to create straighter rows and minimize seams between sections (field assembled). Four alignment pins ensure the outer extruded aluminum rails are aligned, while a draw-screw secures housing-to-housing attachment.

Lengths:

The 3R is available in a minimum 2-foot (nominal) length with additional 2-foot increments available. Longer fixture rows are available and will be configured per ALL factory specifications; typical rows are configured with 4-foot, 6-foot and 8-foot fixtures. Maximum run length on one power feed is 72'. Continuous runs over 72' will require a second feed.

Mounting Method/Hardware:

The 3R is designed for lay-in grid ceilings or "Hard" sheet rock construction. Hard ceiling installations can be supplied for overlapping flange or "Trimless" spackle flange types.

Exterior Finish:

The 3R is available in White and Black polyester powder coat finish to ensure durability.

Integrated Controls:

The 3R is available with optional integrated controls. Sensors are conveniently designed to mount in aperture. For individual fixtures, the sensor is located at the power feed end. For runs, each Starter, Joiner and Ender fixture will be supplied with a discrete sensor that will control that specific fixture within the run.

Shipping:

2-Week lead time for orders up to 1000 Linear Feet.


4-Week lead time for orders with a Black finish.

Lead time for orders greater than 1,000' will be determined at time of order.

Manufactured in the USA:

All ALL Luminaires and Components (with the exception of our LED boards and drivers) are proudly manufactured and assembled in the USA.

MOUNTING DETAILS




MOUNTING DETAILS NOTES


4" GRID CENTERS

FIXTURE ROW LAYOUT: SINGLE UNIT 2' - 4' - 6' - 8' - 10' - 12'


2' FIXTURE




4' FIXTURE




6' FIXTURE




8' FIXTURE



10' FIXTURE




12' FIXTURE




FIXTURE ROW LAYOUT: TWO UNITS 14' - 16'

14' FIXTURE



16' FIXTURE




FIXTURE ROW LAYOUT: THREE UNITS 18' - 20' - 22' - 24'


18' FIXTURE




20' FIXTURE



22' FIXTURE




24' FIXTURE



FIXTURE ROW COMPONENTS

RUN LENGTH (FT)	FIXTURE LENGTHS									JOINER KITS	CEILING CUT OUT LENGTHS
	STARTER	JOINER							ENDER		
	1	2	3	4	5	6	7	8	9		
14	6'	-	-	-	-	-	-	-	8'	1	167.25"
16	8'	-	-	-	-	-	-	-	8'	1	191.25"
18	4'	6'	-	-	-	-	-	-	8'	2	215.25"
20	4'	8'	-	-	-	-	-	-	8'	2	239.25"
22	6'	8'	-	-	-	-	-	-	8'	2	263.25"
24	8'	8'	-	-	-	-	-	-	8'	2	287.25"
26	4'	6'	8'	-	-	-	-	-	8'	3	311.25"
28	4'	8'	8'	-	-	-	-	-	8'	3	335.25"
30	6'	8'	8'	-	-	-	-	-	8'	3	359.25"
32	8'	8'	8'	-	-	-	-	-	8'	3	383.25"
34	4'	6'	8'	8'	-	-	-	-	8'	4	407.25"
36	4'	8'	8'	8'	-	-	-	-	8'	4	431.25"
38	6'	8'	8'	8'	-	-	-	-	8'	4	455.25"
40	8'	8'	8'	8'	-	-	-	-	8'	4	479.25"
42	4'	6'	8'	8'	8'	-	-	-	8'	5	503.25"
44	4'	8'	8'	8'	8'	-	-	-	8'	5	527.25"
46	6'	8'	8'	8'	8'	-	-	-	8'	5	551.25"
48	8'	8'	8'	8'	8'	-	-	-	8'	5	575.25"
50	4'	6'	8'	8'	8'	8'	-	-	8'	6	599.25"
52	4'	8'	8'	8'	8'	8'	-	-	8'	6	623.25"
54	6'	8'	8'	8'	8'	8'	-	-	8'	6	647.25"
56	8'	8'	8'	8'	8'	8'	-	-	8'	6	671.25"
58	4'	6'	8'	8'	8'	8'	8'	-	8'	7	695.25"
60	4'	8'	8'	8'	8'	8'	8'	-	8'	7	719.25"
62	6'	8'	8'	8'	8'	8'	8'	-	8'	7	743.25"
64	8'	8'	8'	8'	8'	8'	8'	-	8'	7	767.25"
66	4'	6'	8'	8'	8'	8'	8'	8'	8'	8	791.25"
68	4'	8'	8'	8'	8'	8'	8'	8'	8'	8	815.25"
70	6'	8'	8'	8'	8'	8'	8'	8'	8'	8	839.25"
72	8'	8'	8'	8'	8'	8'	8'	8'	8'	8	863.25"

FIXTURE LENGTH		
	STARTER	JOINER / ENDER
4'	46.9"	48.0"
6'	70.9"	72.0"
8'	94.9"	96.0"



OVERLAPPING FLANGE CEILING CUT OUT WIDTH	SPACKLE FLANGE CEILING CUT OUT WIDTH
3.4"	4.25"